KOLAR DIVISION.

Dated 8th December 1912.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 18th December 1912, for restoring Sonnangur, Jambukere, Registered No. 215, Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Sonnangur Jambukere, Registered No. 215, Mulbagal Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per*	*Quantity.*
1. Bund—		
Earthwork including watering and tamping ...	... C. yds.	3,162
Do breach	... ,,	1,457
Puddle wall with clay to breach	... ,,	266
Clearing sand to breach and cutting grips, etc. ...	... Lump sum	
Turfing	... Sq. yds.	5,427
Rough stone work, old, with new jelly ...	... C. yds.	793
New stone work	... ,,	1,143
Gravel backing	... ,,	643
Grade stones including bed slabs with figuring and painting...	Each	26
Index stones	... ,,	26
B. M. stones	... ,,	2
Registered Number stone	... ,,	1
Gauge stone	... ,,	1
Date stone	... ,,	1
Cutting big honge trees, removing roots, complete ,etc. ...	Lump sum.	
Consolidating earthwork available from weirs ...	... C. yds.	1,312
2. Sluice No. 1 and No. 2 (quantities noted represent for only one sluice)—		
Earthwork excavation and refilling with watering, etc.	... C. yds.	125
Concrete in surki mortar	... C. ft.	141
Burnt brick in surki mortar	... ,,	536
Burnt stone slabs dressed	... Sq. ft.	225
Plastering with surki mortar	... Sq.	4·00
Wooden plug with iron rod with key, etc., complete	... Lump sum.	
Drilling holes to upper and lower orifices and guide slab	... Lump sum.	
3. Right and left waste weirs—		
Earthwork excavation	... C. yds.	1,322
Burnt brick in surki mortar	... C. ft.	3,816
Burnt stone slabs dressed	... Sq. ft.	617
Providing joggles with cutting groves ..	... Each	61
Plastering with surki mortar	... Sqrs.	21·39
Rough stone work, new	... C. yds.	297
Old stone work with new jelly	... ,,	73
Benching rock	... Lump sum.	

V. AIYASWAMI IYER,
Executive Engineer.